

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2014-15/RD/WORK_INDENT16725/CALL-1

APPROVED SCHEDULE - B

EE/BTP/BMP/E-PMT/10/2014-15, Date: 21.02.2015

Development of Suvarna Mahotsava Ground in ward no 09 Vidyananyapura Sub Division (Change of Work) Improvements to Metalling & Asphaltting at Virupakshapura Maramma Temple to Indaian Express Layout Road in ward no 09 Vidyananyapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				B B UMESHA	
				In Figures	In Words
1	312	Earth work excavation by manual means in Hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work	Cum	111.11	Rupees One Hundred Eleven and Eleven Paise Only
2	1040	Scarifying existing stone metal layer upto 75mm thick along with their bituminous surface, picking up scarified materials and stacking of old serviceable materials with lead of 100m, sequential spreading of the salvaged aggregates with fresh aggregates on prepared base and consolidating as per water bound macadam specifications including cost of all labour etc complete as per specifications and directions of engineer in charge of the work	Sqm	87.07	Rupees Eighty Seven and Seven Paise Only
3	195	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density etc complete as per specifications and directions of engineer in charge of the work	Cum	1510.20	Rupees One Thousand Five Hundred Ten and Twenty Paise Only
4	1300	Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing etc complete as per specifications and directions of engineer in charge of the work	Sqm	12.81	Rupees Twelve and Eighty One Paise Only
5	1300	Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means etc complete as per specifications and directions of engineer in charge of the work	Sqm	78.23	Rupees Seventy Eight and Twenty Three Paise Only



6	32.5	Providing and laying bituminous concrete 40mm thick with 100-120 TPH batch type hot mix plant producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 5.4 to 5.6% of mix and filler, transporting the hot mix to work site, laying with hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desire compaction as per MORTH specification clause No. 500.9 complete In all respects as per specifications. MORTH specification NO. 509, With bitumen 80/100, etc complete as per specifications and directions of engineer in charge of the work	Cum	11621.29	Rupees Eleven Thousand Six Hundred Twenty One and Twenty Nine Paise Only
7	249.6	Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading etc complete as per specifications and directions of engineer in charge of the work	Cum	76.33	Rupees Seventy Six and Thirty Three Paise Only



Signature of the Contractor



Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92